

April 9, 2024
The Town of Plympton-Wyoming
546 Niagara Street
Wyoming, ON
N0N 1T0

Mayor and Councillors:

Re: Whiting Drain Page 1 Amendment for Consideration by Council at the April 10, 2024 Meeting to Consider the Report

Attached is a revised page 1 of the Whiting Drain report for approval and adoption by Council at the April 10, 2024 Meeting to Consider the Report. The original report reference October 26, 2023 drain report, however the revised report was not issued until March 6, 2024.

The line

“Future maintenance works will be assessed out in accordance with the October 26, 2023 drain report.”

Was replaced with

“Future maintenance works will be assessed out in accordance with the **March 6, 2024** drain report.”

If adopted by Council, landowners will be made aware of the change with their Court of Revision notice.

Yours truly,



Michael Gerrits, P. Eng.
M. Gerrits Consulting Inc.

March 6, 2024
The Town of Plympton-Wyoming
546 Niagara Street
Wyoming, ON
N0N 1T0

Mayor and Councillors:

Re: Whiting Drain

September 27, 2023 Council Instructions to Reconsider the Report

In accordance with the instructions received at the September 27, 2023 Council meeting, under Section 57 of the Drainage Act, M. Gerrits Consulting Inc. has revised the September 8, 2023 drain report for reconsideration by Council. The Whiting Drain report has been revised to address three (3) areas of the drain which are failing. All other proposed works under the September 8, 2023 report will be revised for future works, to be completed under maintenance.

At the Meeting to Consider the Report, landowners were informed that the report revisions will address the following items:

- Clarification of existing pipe materials.
- Repair of the failing 1974 CSP outlet pipe between Station 0+116 and Station 0+121.
- Repair of the failing 1974 concrete pipe at Station 0+238.
- Abandon the 1929 drain, complete with the removal of the Egremont Road road crossing tile and structures.
- Removal and replacement of the 1974 Egremont Road road crossing.
- Removal of the proposed Whiting Branch Drain ditch inlet catch basin.
- Future maintenance works to be completed under one contract.
- Future maintenance works will not require a public meeting with all landowners within the watershed.
- Future maintenance works will be assessed out in accordance with the **March 6, 2024** drain report.

Landowners were informed that the report revisions will not address the following items:

- The condition of the existing 1974 concrete tile between Station 0+121 and Station 0+244 is unknown. Currently this section of drain has one known obstruction and a failing Corrugated Steel Pipe (CSP) outlet pipe. Repairs to both of these failures will be completed under this report.
- The failing 1960 tile coupler immediately upstream of the steel casing at +/- Station 0+035.